

Guidelines - Rubbish Chutes

PCFC- Entity (Business Unit) Name : Trakhees (Dept. of Planning & Development)

Department Name : Civil Engineering Department (CED)

Section Name : Inspection & Compliance (Construction Safety)

Document Reference Number : PCFC-TRK-CED-CS-G23

Revision Number : 02

Revision Date : January 2019


Classification : Public





Guidelines – Rubbish Chutes







SELECTION & LOCATION MAINTENANCE

ANCHORAGE WITH BUILDING. AND USE

- Chute must be proprietary design and be installed to the manufacturer's instructions.
- Locate chute in the area where it does not pose to be an obstruction or danger to others.
- Do not drop material to any point outside the building.
- "Homemade" site fabricated chutes should not be used as their strength and performance is unknown
- Worn out parts of chutes must be removed and/ or replaced immediately.
- Carry out weekly inspection of chutes.
- Maintain chutes in good working condition.
- Maintain a written procedure for overcoming possible blockage of chute.
- Ensure that the chute is securely fixed to the permanent structure of the building.
- All material chutes must be entirely closed.
- Area around the discharge end of the chute must be barricaded.





OPENINGS IN CHUTES

GENERAL USE PROCEDURE

DISPLAY OF NOTICES

- All material chutes shall be entirely enclosed except for opening equipped with enclosures at floor level.
- Area around the chute must be protected with toe boards.
- Guardrails must be fitted either side of chute to prevent fall of persons.
- Provide substantial gate installed in each chute at all floor levels.
- When operations are not in process the area surrounding discharge end of a chute shall be securely closed off.

- · Workers must be instructed in the maximum size of material to be placed in the chute.
- If wheel barrows are used to tip rubbish, a timber block must be used to prevent overrun.
- If blockage is suspected use of chute must be stopped.
- A foreman should be appointed as a contact in case of problems with the chute.
- · Display warning sign & notices in languages easily understood by workers.
- Notices shall be displayed on each floor of the building and also at the discharge end.

PCFC-TRK-CED-CS-G23 Rev. 02 / January 2019 Page 2 of 2